

# 300 Watt Flexi RV Kit

2 Panel, MPPT Controller, 12V System



## SOLAR PANEL



### Matrix 150 Watt Flexi Monocrystalline Panel

- Qty 2
- Dimensions: 31.50" x 44.10" x 0.12"
- Voltage: Vmp 26.4V - Voc 31.68V
- Amp: Imp 5.69A - Isc 5.97A
- Weight: 7.27lbs

## CABLE



### 30ft Pair of #10 PV/UV Cable

Positive & Negative 10AWG Cable with MC4 Connectors on one end

## CONTROLLER



### 30A EP-Solar MPPT- Charge Controller

- 12v Peak PV Power Output: 390 Watt
- 24v Peak PV Power Output: 780 Watt
- 150Vdc Solar Panel Input
- 12/24Vdc Battery Output
- Fully User Programmable
- Optional USB to PC Cable and Temp Sensor



### EP-Solar MT50 Remote Display Meter

- Monitors operational data and working status of the charge controller

## HARDWARE



### 30A 12/24V Inline Resettable Circuit Breaker System

Qty: 2



### Lepage QUAD Max Sealant

White  
Qty: 1



### MC4 PV Connectors

Male & Female  
Qty: 1



### Ring Terminals

10AWG, 5/16" ring size with PVC cover  
Qty: 2



### 8" Off-Grid Kit Cable Tie

Qty: 20



### 5/8" Off Grid Kit Screw

Qty: 24